BRUHAT BANGALORE MAHANAGARA PALIKE
DASARAHALLI ZONE

Office of the Executive Engineer
Electrical Division, Dasarahalli Zone
Bruhath Bengaluru Mahanagara Palike

"DTS for Kind Approval"

Name Of Work :- Annual Maintenance of Street Lights Package D-2 Ward No 13 Mallasandra

Sl. No	Qty	Description Of Work	Unit	Approved Rates	
				In figures	In words
1	148	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below i) Poles with 36/40 W fluorescent tube light street lighting system	Each	685 45	Rupees Six Hundred Eighty Five And Paise Forty Five Only
2	89	Poles with 125 W MV light Park lighting system	Each	756 29	Rupees Seven Hundred Fifty Six And Paise Twenty Nine Only
3	1323	Poles with 250W HPSV light street lighting system	Each	1019 41	Rupees One Thousand Nineteen And Paise Forty One Only
4	58	Poles with 400 watts HPSV light street lighting system	Each	1118 08	Rupees One Thousand One Hundred Eighteen And Paise Eight Only
5	80	Poles with 24 W LED light street lighting system	Each	880 01	Rupees Eight Hundred Eighty And Paise One Only
6	184	Poles with 65 W LED light street lighting system	Each	1147 43	Rupees One Thousand One Hundred Forty Seven And Paise Forty Three Only
7	134	Poles with 90 W LED light street lighting system	Each	1377 66	Rupees One Thousand Three Hundred Seventy Seven And Paise Sixty Six Only
8	15	Operation and maintenance of Manual and Automatic Timer Switching circuits including replacement of electrical gadgets, such as MCB's Contactors, Timer, Cut-outs, wiring connector and M S Box with proper insulation etc , complete	Each	3115 44	Rupees Three Thousand One Hundred Fifteen And Paise Forty Four Only
9	89	B Work to be carried out as per requirement & actuals and as per the direction of the In charge engineer. Painting of existing street light pole after scrapping the old paint and painted with suitable colour enamel/Silver paint including coping/footing of the pole a)5 mtr pole	Each	550 00	Rupees Five Hundred Fifty Only
10	12	c) 8 Mtr and above street light pole	Each	770 00	Rupees Seven Hundred Seventy Only
11	33	Moulded Case Circuit Breaker (MCCB) Three Pole 100Amps 25kA	Each	2718 00	Rupees Two Thousand Seven Hundred Eighteen Only
	33	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop-In & Loop-Out terminals for 10 Sqmm / 25 Sqmm 3 5 C Al/Ar / Cu/Ar Cable and branch out 2 5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof) rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic polyamide glands and/or grommets 200mmx200mmx98mm	Each	2178 00	Rupees Two Thousand One Hundred Seventy Eight Only
	1000	Supplying of 1 1KV grade Aerial Bunched Cable Stranded & Compacted Aluminum Phase Conductor, and Stranded Messenger Conductor with all aluminum Alloy, Phase Conductor is insulated with XLPE Compound, insulated Messenger with specified IS-14255 1995 & confirming to GTP of GROUP-A 2 X 25 + 1 X 25 SQ MM	Mtrs	143 00	Rupees One Hundred Forty Three Only

" DTS Approved "

EXECUTIVE ENGINEER (ELEC)
BBMP, Dasarahalli Zone

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

Scanned by CamScanner